

PRELIMINARY SITE LAYOUT - 9-5-18

BASED ON SITE PLANS RECEIVED 7-10-18

WET WELL DEPTH: 19.73'

DISTANCE TO TERMINATION: 14'

NOTE: CABLES TO BE TERMINATED IN APPROVED JUNCTION BOX OR CONTROL PANEL

APPROX. CABLE LENGTH NEEDED: 33'

PUMP CABLE LENGTH: 50'

TRANSDUCER CABLE LENGTH: 50'

FLOAT CABLE LENGTH: 65'

FOR DESIGN REVIEW

- NOTE: SITE MATERIALS, DESIGN INFORMATION, AND SERVICES **NOT** SUPPLIED BY ROMTEC UTILITIES:
- GRADING
 - WIRING AND CONDUIT
 - FENCING AND PAVING
 - SITE LIGHTING
 - SITE UTILITIES (WATER, POWER, ETC)
 - SCADA ANTENNA
 - ALL ON-SITE INSTALLATION

