

Control Panel Scope of Supply
McCORMICK LS#1
PORT ORCHARD, WA
5/16/18

General information

- ELECTRICAL SERVICE - 480V, 3 Phase
- PUMPS - (3) 125HP, 460V, 3 PH, 154FLA, TRIPLEX configuration
- PUMPS - VAUGHN 4P SERIES

Liquid level sensing

- PRIMARY LEVEL SENSING - FMX21 PRESSURE TRANSDUCER
- BACKUP LEVEL SENSING - SIEMANS XPS-15
- TERTIARY BACKUP CONTROL - 10PT. CONDUCTIVE PROBE
- FLOOD DRY PIT - SINGLE SENSOR PROBE

Station Control Panel

Qty.	Description
1	NEMA 12 Painted Steel, 30"W X 90"H X 20"D MCC section.
1	18" X 12" folding shelf
1	TVSS advanced surge suppression
1	CompactLogix Processor L36ERM
4	Allen-Bradley Compact I/O Digital Input, 16pt. P/N 1769-IQ16
2	Allen-Bradley Compact I/O Analog Input, 4Ch P/N 1769-IF4I
1	Allen-Bradley Compact I/O Analog Output, 4Ch P/N 1769-OF4
2	Allen-Bradley Compact I/O Digital Output, 16pt. P/N 1769-OB16
1	Allen-Bradley Compact 24V Power Supply P/N 1769-PB4
1	Allen-Bradley 7" Operator Touch Screen #2711R-T7T
1	Allen-Bradley 1609P3000N UPS
1	Allen-Bradley Port Ethernet Switch P/N 1783-BMS12T4E2CGL
2	Allen-Bradley DC Power Supply P/N 1606-XLB240E
1	Allen-Bradley DC Power Supply Redundancy Module P/N1606XLSRED
1	Bulkhead Ethernet port
1	Siemens HydroRanger -200
2	Modem Telenetics IG96HFP-LV. (1-Spare) (Phone line by others)
1	DF1 to Ethernet/IP Router Prosoft #PLX51-DF1-ENI
3	HOA selector switches for manual pump control (1 per pump)
3	Elapsed time meters, one per pump
3	Pump cycle counters
2	MTRA5 relays, 24VDC coils
	- MTR = Pumps Stop/High Level
	- MTR = Pumps Start/Alarm
1	E&H Promag Flow Transmitter
1	Branch circuit breakers mounted on the dead front to control the following functions:
	1. Convenience outlet 5A
1	Alarm beacon red flashing light
1	Audible Horn with push to silence button Silence button mounted on panel exterior..
3	Thermal/Seal Fail detection for Vaughn Pumps.
3	"Run" pilot light, green, push to test, located on dead front
3	"Pump Fault" pilot light, red, push to reset, located on dead front.
1	"High Level" pilot light, red, push to test, located on dead front
1	"Redundant Hi Level" pilot light, red, push to test, located on dead front
1	Remote switch (ON/OFF/REMOTE) for fans located at manway access
1	Blower On/Off Selector Switch mounted on dead front with Pilot Light
1	2-Position selector switch for "Intrusion Enable".
1	"GO - NO GO" pilot indicating light station for gas detection.
1	"Operator In Trouble" push-button mounted in dry pit.
1	"Control Power Okay" pilot light, white, push to test, located on dead front
1	Intrinsically Safe Barrier for primary level sensing
1	5 Ch. Barrier for tertiary level sensing
2	Intrinsically Safe Barriers for pump service hatch intrusion switches
1	Intrinsically Safe Barriers for pressure transmitter
1	Panel interior LED light with door switch
1	"Dry pit flooded" PTT light
1	Control panel thermostat #KTD-267
1	Signal converter #XNPNPNP
1	Warning arc flash and shock hazard label Emedco #QS3743 or equivalent.
1	Electric Shock Hazard. Main disconnect switch does not remove UPS output power.
	Turn off UPS before servicing. or equivalent
*	All pilot light indicators to be LED
	Prefabricated wiring whips between the control panel and MCC devices.

Digital Inputs - Slot 1

DI0	Phase Failure
DI1	Intrusion Enable
DI2	Generator Running
DI3	Generator Warning
DI4	Generator Fault
DI5	Generator Low Fuel
DI6	Generator Fuel Leak
DI7	ATS in Emergency
DI8	Meter Vault Intrusion
DI9	Valve Vault Intrusion
DI10	Panel Intrusion
DI11	Wet Well Intrusion
DI12	Dry Pit Intrusion
DI13	Pumps Running from back up controller (HydroRanger)
DI14	High Level Alarm from back up controller (HydroRanger)
DI15	Back up controller failed (HydroRanger)

Digital Inputs - Slot 2

DI0	Pump 1 Running
DI1	Pump 1 Fault
DI2	Pump 1 Reset
DI3	Pump 1 in Auto
DI4	Pump 1 in Hand
DI5	Pump 1 Overtemp
DI6	Pump 1 Leak Seal
DI7	Pump 1 Check Valve
DI8	Pump 2 Running
DI9	Pump 2 Fault
DI10	Pump 2 Reset
DI11	Pump 2 in Auto
DI12	Pump 2 in Hand
DI13	Pump 2 Overtemp
DI14	Pump 2 Leak Seal
DI15	Pump 2 Check Valve

Digital Inputs - Slot 3

DI0	Pump 3 Running
DI1	Pump 3 Fault
DI2	Pump 3 Reset
DI3	Pump 3 in Auto
DI4	Pump 3 in Hand
DI5	Pump 3 Overtemp
DI6	Pump 3 Leak Seal
DI7	Pump 3 Check Valve
DI8	Emergency Stop
DI9	Dry Pit Flood Switch
DI10	Dry Pit Smoke Alarm
DI11	Building Smoke Alarm
DI12	Gas Detector "OK"
DI13	Gas Detector "Fault"
DI14	Fans Auto
DI15	Fans On

Digital Inputs - Slot 4

DI0 Fans Remote
DI1 Fans On
DI2 UPS Alarm
DI3 DC Power Supply "PS1" OK
DI4 DC Power Supply "PS2" OK
DI5 Control Power OK
DI6 Redundant High/High Alarm
DI7 Pumps Running on Tertiary Back-up System
DI8
DI9
DI10
DI11
DI12
DI13
DI14
DI15

Digital Outputs - Slot 5

DO0 Pump 1 Call
DO1 Pump 2 Call
DO2 Pump 3 Call
DO3 Pump 1 Fault
DO4 Pump 2 Fault
DO5 Pump 3 Fault
DO6 Pump 1 Reset
DO7 Pump 2 Reset
DO8 Pump 3 Reset
DO9 Alarm Light
DO10 Alarm Horn
DO11 Gas Detection Fault Light
DO12 Gas Detection OK Light
DO13 Exhaust Fan Run
DO14 Spare
DO15 Spare

Digital Outputs - Slot 6

DO0 Spare Relay
DO1 Spare Relay
DO2
DO3
DO4
DO5
DO6
DO7
DO8
DO9
DO10
DO11
DO12
DO13
DO14
DO15

Analog Output - Slot 7

AO0 Pump 1 Speed Reference (4-20mA)
AO1 Pump 2 Speed Reference (4-20mA)
AO2 Pump 2 Speed Reference (4-20mA)
AO3 Spare

Analog Input - Slot 8

AI0 Pressure Transducer (4-20mA)
AI1 Hydoranger (4-20mA)
AI2 Force Main Pressure Transmitter 94-20mA)
AI3 Flow Meter (4-20mA)

Analog Input - Slot 9

AI0 Control Panel Temperature (4-20mA)

AI1	Dry Pit Temperature (4-20mA)
AI2	Generator Fuel Level (4-20mA)
AI3	Spare

HMI TERMINAL

- Level setpoints
- Level control
- Alarms
- Pump status
- Pump control
- Exhaust fan status
- Event alarm log with date and time stamp
- Elapsed time meters
- Set-up