



Scope of Products and Services

Romtec Utilities, Inc. | 18240 North Bank Road | Roseburg, OR 97470 | 541-496-9678
 Email: RUsales@romtec.com | www.romtecutilities.com

PART 1: OVERVIEW

1.1 Description

Project Name: Crowder Construction (Stevens Creek) – Deflector Panel
 Location: Charlotte, NC
 Date: 2/28/2020

1.2 Project Overview

This is a complete, packaged deflector panel intended to serve the Stevens Creek lift station system for the purpose of deflecting inflow from the system inlet down into the wet well.

1.3 Design Overview

For this project, Romtec Utilities is proposing to supply a complete packaged deflector panel assembly for the Stevens Creek project. Romtec Utilities based this scope of supply on data and design criteria received 02-26-20 provided by Crowder Construction.

Romtec Utilities has designed the trash basket assembly to match as closely as possible the given design criteria.

Wet Well ID: 12'

Invert Diameter: 24"

Depth of Invert: 32.64'

1.4 Overview of Scope

- A. Romtec Utilities has reviewed the provided data and design criteria to ensure that the deflector panel assembly meets the stated requirements for the project.
- B. Romtec Utilities will supply the deflector panel assembly as described below and in the attached component drawing.
- C. Romtec Utilities will supply all mounting hardware.
- D. Romtec Utilities does not perform any construction at the project site.

PART 2: PRODUCT AND SERVICES

The following is a general summary of the components and services Romtec Utilities is proposing to supply:

2.1 Delivery Services

- A. Romtec Utilities' will coordinate shipping to Charlotte, NC.

2.2 Deflector Panel Assembly

The following are the associated pump items Romtec Utilities will be supplying and integrating:

- A. Romtec Utilities will supply one deflector panel assembly including: panel, mounting brackets, and mounting hardware.
- B. The deflector panel assembly will be shipped as a single unit accompanied by a package of accessory hardware. Installation is required onsite by the installing contractor.
- C. See attached component drawings for more details.

ITEM	QTY	STOCK NUMBER	DESCRIPTION
1	1	15-DP120800	DEFLECTOR PANEL ASSEMBLY - 12FT DIA WELL X 8FT H

2.3 Warranty

- A. The deflector panel assembly shall be warrantied according to Romtec Utilities’ standard warranty. The warranty period will begin upon installation of assembly, or 18 months from delivery of the assembly or the date the assembly was ready to deliver, whichever is earlier.